

# APPROVED

Date 12-16-97 RRC  
**CALHOUN COUNTY**  
**REMONUMENTATION.**

**CALHOUN COUNTY REMONUMENTATION**  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
 CALHOUN COUNTY  
 RECORDED

For corners in

<u>CALHOUN</u> (County)	Located In:	Corner Code #
MARENGO		
1. Public Land Survey	T <u>2S</u> R <u>5W</u>	<u>I-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

19 DEC 97 2:38 P.M.

ANNE B. NORLANDER  
 CLERK - REGISTER OF DEEDS

LIBER **1985** PAGE **526**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, MICHAEL A. GROAT, in a field survey on DECEMBER 2, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22	⊕	23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

LUCIUS LYON, DEPUTY SURVEYOR, 1825, SET POST, B. OAK, 9", S6°W, 13 LKS., B. OAK, 13", N8°E, 36 LKS.

J.M. GIFFORD, 1889, FOUND STUMP OF BEARING TREE, CORNER FELL ON SW SIDE OF 24" OAK

D. DEKEYSER, MARCH 2, 1987, FOUND 1-1/2" IRON IN MON. BOX, 1' BELOW GRAVEL IN LINE WITH FENCES NORTH AND SOUTH. 78.3' NORTH OF CENTERLINE OF EAST BOUND I-94, 28.41' SOUTH OF SURVEY CENTERLINE OF I-94.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1-1/2" IRON IN MON. BOX CALLED FOR BY DEKEYSER. NO FIRECLAY COULD BE FOUND DUE TO CONSTRUCTION OF I-94. ACCEPTED THE POSITION OF THE IRON AS THE BEST LOCATION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET A BERNTSEN MONUMENT IN THE MONUMENT BOX.

NORTH, FACE OF ANGLE IRON FENCE POST, 96.31'  
 EAST, FACE OF CENTER SUPPORT OF 22-1/2 MILE ROAD BRIDGE, 1312.75'  
 SOUTH, FACE OF ANGLE IRON FENCE POST, 153.33'  
 S65°W, MOST NORTHERLY POST OF ROAD SIGN, 319.20'  
 28.41' SOUTH OF SURVEY CENTERLINE OF I-94  
 78.3' NORTH OF CENTERLINE OF EASTBOUND LANE



Signed by [Signature] Date DECEMBER 10, 1997

Surveyor's Michigan License No. 39079

**SURVEY & REMONUMENTATION**

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1976  
 REVISED JAN., 1983  
 REVISED OCT., 1986

APR 07 1998

SECTION