

APPROVED

Date 3-19-97
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTAION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

31 MAR 97 11:39 A.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER 1922 PAGE 729

Register of Deeds Stamp & File Number

For corners in

<u>CALHOUN</u>	Located In:	Corner Code #
(County)		
Marengo Township		
1. Public Land Survey	T <u>2S</u> R <u>5W</u>	<u>1-9</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael A. Groat, in a field survey on March 11, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9									⊙				
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Lucius Lyon, Deputy Surveyor, 1825, set post
B. Oak, 6", S27°E, 173 Lks, B. Oak, 10", N41½°E, 91 Lks.

Gifford, 1890, Found plow point with brick around that was set by G.D. Lewis, former County Surveyor. Gifford dug up the plow point and set a tile.
Double yellow oak, 14" N10°E, 38 Lks

May 31, 1972, Milton DeKeyser, R.L.S. #12019, found hollow tile and plow point, centerline of U.S. 12 South, 349.48 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found plow point and tile with brick around. Fence North and South. Accepted the tile as a careful and faithful perpetuation of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument with standard Calhoun County brass cap stamped with P.S. #39079 and corner information.

Nail and tag in 10" Ash, S5°E, 11.00 feet
Nail and tag in 14" Ash, S16°W, 1.98 feet
Nail and tag in 18" Maple, N75°W, 3.26 feet
Nail and tag in 16" Ash, N70°W, 6.01 feet
Carsonite sign on North side
Centerline of U.S. 12, South, 349.48 feet



Signed by Michael A. Groat
Surveyor's Michigan License No. 39079

Date March 19, 1997

SURVEY & REMONUMENTATION

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED JAN., 1963
REVISED OCT., 1966

APR 07 1998

SECTION