

APPROVED

Date 11/25/97 RRC
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

1 DEC 97 4:51 P.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER 1980 PAGE 509

Register of Deeds Stamp & File Number

For corners in
CALHOUN

Located In: Corner Code #

(County)

MARENGO TOWNSHIP

1. Public Land Survey

T 2S R 5W Corner Code # J-7

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, MICHAEL A GROAT, in a field survey on OCTOBER 10, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7										⊙			
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL SURVEY BY LUCIUS LYON, DEPUTY SURVEYOR, SET POST 40.06 CHAINS EAST OF THE NORTHWEST CORNER OF SECTION 23; TAMARACK, 8", S70°W, 17LKS; TAMARACK, 5", S30°E, 9LKS.

J.M GIFFORD IN 1880, RE-ESTABLISHED THE CORNER FROM BOTH LYON BEARING TREES, SET TILE; MAPLE, 12", N9-1/2°W, 61LKS, MAPLE, 16", N61°E, 79 LKS.

1984, BRYAN REYNOLDS, P.S. #31602, FOUND A 5/8" IRON IN A MONUMENT BOX, 38" MAPLE, N75°W, 85.90'; 28" MAPLE, N20°W, 43.32'; 6" LOCUST, S65°W, 63.86'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 5/8" IRON IN MONUMENT BOX. EXCAVATED AND FOUND A 1' LONG NAIL. THIS IS IN A FILL AREA AND NOTHING ELSE COULD BE FOUND. ONLY ONE WITNESS TREE FROM PART 'A' REMAINED. ACCEPTED THE 5/8" IRON AS THE BEST POSSIBLE LOCATION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET A BERNTSEN MONUMENT IN A MONUMENT BOX IN PLACE OF THE IRON

- NAIL AND TAG IN A 38" MAPLE, N80°E, 86.11'
- NAIL AND TAG IN A 30" R. OAK, S70°E, 110.2'
- NAIL AND TAG IN A 10" MAPLE, N3°W, 52.05'
- NAIL AND TAG IN A 10" WILLOW, N50°W, 39.85'



Signed by [Signature] Date NOVEMBER 25, 1997

Surveyor's Michigan License No. 39079

SURVEY &
REMONUMENTATION

APR 07 1998

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1976
REVISED JAN., 1983
REVISED OCT., 1986

SECTION