

**SURVEY &
REMONUMENTATION**

APR 07 1998

APPROVED

SECTION

Date 11/25/97 RRC
**CALHOUN COUNTY
REMONUMENTATION.**

**CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

1 DEC 97 4:51 P.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER 1980 PAGE 510

Register of Deeds Stamp & File Number

For corners in
CALHOUN

Located In: Corner Code #

(County) MARENGO TOWNSHIP			
1. Public Land Survey	T <u>2S</u> R <u>5W</u>	<u>J-9</u>	
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, MICHAEL A. GROAT, in a field survey on OCTOBER 1, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	16		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL SURVEY BY LUCIUS LYON, DEPUTY SURVEYOR, SET POST 40.05 CHAINS EAST OF SOUTHWEST CORNER OF SECTION 23. W. OAK, 20", N40°W, 40 LKS; W. OAK, 19", S50°E, 40 LKS.

J.M. GIFFORD IN 1889, SET TILE AND NOTED THAT "WELLS" ESTABLISHED THE CORNER IN 1880. APPLE, 8", S64-1/4°E, 104 LKS; HICKORY, 12", S84-1/2°W, 207 LKS.

JOHN ALDEN, P.S., FOUND PIECES OF TILE AROUND CONCRETE FENCE POST, 10" PINE, N10°E, 21.3', 10" APPLE, N70°W, 66.2', C.P. CO. MARKER, SOUTH, 318'.

MILTON DEKEYSER, P.S. #12019, IN LCRC DATED 12-12-79 AND RECORDED IN LIBER 1220, PAGE 847, FOUND CONCRETE FENCE POST AND USED SAME WITNESSES AS ABOVE.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CONCRETE FENCE POST WITH PIECES OF TILE. ACCEPTED THIS AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

THE CORNER IS A CONCRETE FENCE POST WITH A CARSONITE MARKER BESIDE.

NAIL AND TAG IN 8" PINE, N35°E, 21.7'
NAIL AND TAG IN 10" PINE, N70°E, 27.5'
NAIL AND TAG IN 10" PINE STUMP, NORTH, 37.1'
NAIL AND TAG IN 10" PINE, N10°E, 39.10'
NAIL AND TAG IN 15" PINE, N15°E, 58.10'



Signed by M.A.G.
Surveyor's Michigan License No. 39079

Date NOVEMBER 25, 1997