

APPROVED

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

Date 5-21-97
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

23 MAY 97 4:30 P.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER 1934 PAGE 953

Register of Deeds Stamp & File Number

For corners in
CALHOUN

Located In:

Corner Code #

(County)

MARENGO TOWNSHIP

1. Public Land Survey

T 2S R 5W K-7

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, MICHAEL A GROAT, in a field survey on MAY 8, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	H
1													
2	6			5			4			3			2
3													
4	7			8			9			10			11
5													
6	18			17			16			15			14
7													13
8	19			20			21			22			23
9													
10	30			29			28			27			26
11													
12	31			32			33			34			35
13													36

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL SURVEY BY LUCIUS LYON, DEPUTY SURVEYOR, SET POST, W. OAK, 7", S82½°W, 39 LINKS; B.OAK, 6", NORTH 47 LINKS

J.M. GIFFORD, 1889, NOTED THAT THE CORNER HAD BEEN RESTORED AND PLACED BY B.F. WELLS, COUNTY SURVEYOR. SET TILE IN SAME PLACE; HICKORY, 20", S61½°E, 92 LINKS, Y.OAK, 5", S61½°W, 92 LINKS.

1959, M.S.H.D. WITNESS CARD HAD A 1½" IRON AND SET A MONUMENT BOX. 18" HICKORY, S87°E, 77.95'; 6" OAK, N64°E, 59.85'; 6" OAK, S26°W, 66.77'; STEEL CORNER POST, NORTH, 33.55'

MILTON DEKEYSER, P.S.#12019, IN LCRC DATED 9/20/73 AND RECORDED IN L.1027, P.63, STATED "FOUND NOTHING, ROAD RAISED 10'. RESTROED USING PREVIOUS SURVEY BY J.H. ALDEN." SET ½" IRON. CORNER FENCE POST, N2°W, 33.65'; U.P. N65°E, 72.42'; U.P., S15°E, 118.67', GAS WARNING SIGN POST, S50°W, 111.69'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND A MONUMENT BOX WITH IRON. FOUND BROKEN HOLLOW TILE WITH ROCKS AROUND. UNSURE WHY DEKEYSER SAID THE ROAD HAD BEEN RAISED 10', DID NOT APPEAR TO HAVE BEEN RAISED. THERE IS A GAS PIPELINE RUNNING UNDER THE CORNER AND THE IRON REFERRED TO BY THE M.S.H.D. MAY HAVE BEEN DISTURBED THEN. CHECKED INTO THE REMAINING WITNESSES FROM PART 'A' AND ACCEPTED THIS POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET A BERNTSEN MONUMENT IN A MONUMENT BOX AND STAMPED CORNER INFORMATION AND LICENSE NUMBER IN BRASS CAP.

WITNESSES TO BERNTSEN MONUMENT:

FACE OF	2" STEEL CORNER POST	NORTH	33.65'
FACE OF	RAIL ROAD IRON POST	N70°E	34.35'
FACE OF	RAIL ROAD IRON POST	S50°E	59.50'
NAIL AND TAG	RAIL ROAD TIE FENCE POST	S80°W	53.45'

Signed by _____ Date MAY 21, 1997

Surveyor's Michigan License No. 39079

SURVEY &
REMONUMENTATION



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

APR 07 1998

REVISED JAN. 1983
REVISED OCT. 1986

SECTION