

APPROVED

Date 5-21-97

CALHOUN COUNTY REMONUMENTATION

For corners in CALHOUN

CALHOUN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN CALHOUN COUNTY RECORDED

23 MAY 97 4:30 P.M.

ANNE D. NORLANDER CLERK - REGISTER OF DEEDS

LIBER 1934 PAGE 954

Register of Deeds Stamp & File Number

Form with fields for Located In: (County) MARENGO TOWNSHIP, Corner Code # K-9, and numbered sections 1-5 for survey details.

I, MICHAEL A. GROAT, in a field survey on MAY 8, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13, containing numbers 1-36 and a circled 'X' at row 9, column J.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL SURVEY BY LUCIUS LYON, DEPUTY SURVEYOR, SET POST; W. OAK, 12", S63°W, 24 LINKS; W. OAK, 12", S81½°E, 133 LINKS

J.M. GIFFORD IN 1889 NOTED THAT THIS CORNER WAS ESTABLISHED BY B.F. WELLS, COUNTY SURVEYOR; S. MAPLE, 8", S52½°W, 46 LINKS; S. MAPLE, 8", N17½°W, 122 LINKS

J.H. ALDEN, REGISTERED SURVEYOR, 1964, "IRON IN TILE"; 34" MAPLE, S52°30'W, 30.40'; 31" MAPLE, S30°E, 53.73'; 20" MAPLE, N10°30'W, 112.25'; 22" ELM, N14°E, 110.00'

MILTON DEKEYSER, P.S.#12019, IN LCRC DATED FEBRUARY 1, 1973 & RECORDED IN L.1032, P.617, "IRON IN TILE". USED SAME WITNESSES AS ALDEN IN '64 BUT ADDED A 3" HICKORY, N50°E, 41'

R.R. CARR, P.S.#20704, IN LCRC DATED MARCH 26, 1990 AND RECORDED IN L.1525, P.529, "1" SOLID IRON IN TILE IN CENTERLINE OF ROAD"; NEW WITNESS: 40" MAPLE, S30°E, 87.25'; 20" ELM, EAST, 35.46'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND A 1" IRON INSIDE A HOLLOW TILE IN THE CENTERLINE OF THE NORTH-SOUTH ROAD. EXCAVATED AND FOUND 3 SECTIONS OF HOLLOW TILE STACKED ON EACH OTHER. CHECKED INTO WITNESSES FROM PART 'A'.

ACCEPTED THIS POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE CORNER PERPETUATED BY B.F. WELLS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET A BERNTSEN MONUMENT IN MONUMENT BOX IN PLACE OF PIPE AND TILES. STAMPED SECTION INFORMATION AND LICENSE NUMBER ON BRASS CAP.

WITNESSES TO BERNTSEN MONUMENT:

NAIL 36" MAPLE S60°W 29.5' (CARR)
NAIL AND TAG 24' MAPLE S10°E 87.45'
NAIL AND TAG 4" MAPLE N80°E 23.4'
FACE OF 6" WHITE CEDAR N60°W 28.55'
IN CENTERLINE OF NORTH-SOUTH ROAD AND 464+- NORTH OF CENTERLINE OF MICHIGAN AVE.

Signed by [Signature] Date MAY 20, 1997

Surveyor's Michigan License No. 39079 SURVEY & REMONUMENTATION

