

APPROVED

Date Aug 21 1996  
CALHOUN COUNTY  
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &  
REMONUMENTATION

MAR 21 1997

COMMISSION

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

24 SEP 96 10:54 A.M.

ANNE B. NORLANDER  
CLERK - REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

Calhoun

Located In:

Corner Code #

Marshall Twp.

- |                                    |                           |            |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey              | T <u>2</u> S R <u>6</u> W | <u>A-5</u> |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

I, Donald J. Davis, in a field survey on August 10, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Lyon in 1825.

Resurvey by Gifford in 1890. Corner set 72 links south of Emmett corner (M-5).

8" Tamarack N 54° E 32 links.

5" Tamarack N 22° W 25 links.

DeKeyser set 3/4" pipe 47.5 feet south of Emmett corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" pipe 21.5' south of centerline of H Drive North.  
47.5 feet south of SE corner (M-5) of Section 12, Emmett Twp.

Accepted as good location of SW corner Section 7 (A-5).

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

MARSHALL TWP.

LIBER 1887 PAGE 964

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument, 21.5' south of centerline H Drive North; 47.5' south of SE corner Section 12, (M-5) of Emmett Twp., T2S, R7W.

Nail & Tag 6" Tamarack S 5° W 3.95'

Nail & Tag 10" Tamarack S 70° W 30.00'

Nail & Tag 10" Tamarack S 10° E 11.80'

Nail & Tag 18" Poplar N 40° W 85.30'



Signed by Donald J. Davis  
Donald J. Davis  
Surveyor's Michigan License No. 17617

Date August 16, 1996