

SURVEY & REMONUMENTATION

MAR 21 1997

COMMISSION

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

24 SEP 96 10:54 A.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

Register of Deeds Stamp & File Number

APPROVED
Date Aug 21 1996
**CALHOUN COUNTY
REMONUMENTATION.**

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| | | |
|---------------------------------------|--------------------------|---------------|
| Calhoun (County) Marshall Twp. | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>2S</u> R <u>6 W</u> | <u>A-8</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

Marshall Twp.

I, Donald J. Davis, in a field survey on August 10, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Original survey by Lyon in 1825. (no corner set).
Resurvey by Gifford in 1890, No West 1/4 Post set.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 3/4" pipe 34.32' South of Emmett corner as established in 1976 during survey of Section 24, of Emmett Twp.
Accepted as good location of West 1/4 Post of Section 19.

LIBER 1887 PAGE 962

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set Berntsen monument with graphite marker at location.
Fence East and West.
Nail & Tag 8" Poplar N 15° E 141.00'
Nail & Tag Tree of Heaven N 80° W 154.50'
Nail & Tag 8" Poplar S 15° W 64.30'
Nail & Tag 8" Poplar S 30° E 62.30'



Signed by Donald J. Davis
Surveyor's Michigan License No. 17617

Date August 12, 1996