

MAR 2 1 1997

**APPROVED**

Date SEPT 18 1996

**CALHOUN COUNTY REMONUMENTATION.**  
For corners in

**CALHOUN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
COMMISSION**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

24 SEP 96 10:54 A.M.

ANNE B. NORLANDER  
CLERK - REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Calhoun (County)	Located In:	Corner Code #
Marshall Twp.		
1. Public Land Survey	T <u>2</u> S R <u>6</u> W	C-9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Marshall Twp.

I, Donald J. Davis, in a field survey on August 27, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Lyon in 1825.  
Resurvey by Gifford in 1890, tile set.  
Tile found and concrete monument set by Chase in 1937. RR spike set in pavement over monument. RR spike found in 1972 by De Keyser. Recorded in LCRC Liber 992, page 44.  
RR spike found in 1974 by Davis, recorded in LCRC Liber 1037, page 41.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found RR spike in pavement.  
Excavated and found 5" square concrete monument under spike, 1½' below surface.  
Accepted as good preservation of corner location.

LIBER 1887 PAGE 965

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument in monument box.  
6' East of centerline of paving.  
SW corner brick pillar N 40° E 55.80'  
Nail & Tag power pole S 70° E 22.44'  
Nail & Tag 12" Red Oak S 35° E 56.37'  
Nail & Tag 10" Cherry S 15° E 98.62'



Signed by Donald J. Davis  
Donald J. Davis  
Surveyor's Michigan License No. 17617

Date September 9, 1996