

**SURVEY &  
REMONUMENTATION.**

MAR 21 1997

**APPROVED**  
Date SEP 18 1996  
**CALHOUN COUNTY  
REMONUMENTATION.**

CALHOUN COUNTY REMONUMENTATION  
**LAND CORNER RECORDATION CERTIFICATE** COMMISSION  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Calhoun</u> (County)	Located In:	Corner Code #
Marshall Twp.		
1. Public Land Survey	T <u>2</u> S R <u>6</u> W	<u>C-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

24 SEP 96 10:56 A.M.

ANNE B. NORLANDER  
CLERK - REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Donald J. Davis, in a field survey on August 27, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Marshall Twp.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Lyon in 1825.  
Resurvey by Gifford in 1890, tile set.  
Tile found by Chase in 1937.  
NW corner house SE 127.3'  
12" Maple South 20.3'  
8" Maple N 70° W 22.5'

Found by Alden in 1958, set pipe.  
Pipe found in 1973 by Davis.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" Pipe in hollow tile.  
Accepted as good location of original corner.

LIBER 1887 PAGE 970

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument and monument box in gravel shoulder at road corner.  
Nail & Tag 40" Maple N 20° W 46.83'  
Nail & Tag 16" Maple N 70° W 22.91'  
Nail & Tag 28" Maple South 20.42'  
Nail & Tag 24" Maple S 55° E 34.87'



Signed by

*Donald J. Davis*

Date September 9, 1996

Surveyor's Michigan License No. Donald J. Davis 17617