

**SURVEY &
REMONUMENTATION**

MAR 21 1997

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE COMMISSION
Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED
Date SEPT 18 1996
**CALHOUN COUNTY
REMONUMENTATION.**

For corners in

<u>Calhoun</u> (County)	Located In:	Corner Code \neq
<u>Marshall Twp.</u>		
1. Public Land Survey	T <u>2</u> S R <u>6</u> W	D-9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

24 SEP 96 10:53 A.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Donald J. Davis, in a field survey on August 21, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Marshall Twp.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Lyon in 1825.
Resurvey by Gifford in 1890. 12" Burr Oak N 84° W 43 links, 12" Burr Oak N 84° E 43 links.
Concrete monument set in 1937 by Chase.
18" Burr Oak N 83° W 31', 12" Burr Oak N 3° W 106', 3' East N & S fence in line with fence West.
Concrete monument found by Carr in 1971. Recorded in 1972 by DeKeyser, Liber 992, page 44.
18" Burr Oak N 83° W, 31.00', 12" Burr Oak N 3° W 106.00', 3' East of N & S fence, fence West.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found concrete monument at location as witnessed and recorded.

LIBER 1887 PAGE 966

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

4" concrete monument.
3' East of North & South fence, in line with fence West.
Nail & Tag Twin 10" Cherry 16.37'
Nail & Tag 8" Burr Oak North 61.85'
Nail & Tag 48" Burr Oak N 83° W 31.45'
Angle iron post West 3.35'



Signed by Donald J. Davis
Donald J. Davis 17617
Surveyor's Michigan License No. _____

Date September 11, 1996