

**SURVEY &  
REMONUMENTATION**

CALHOUN COUNTY REMONUMENTATION **MAR 21 1997**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

**APPROVED**

Date SEPT 18 1996

**CALHOUN COUNTY  
REMONUMENTATION.**

For corners in

<u>Calhoun</u> (County)	Located In:	Corner Code #:
1. <u>Marshall Twp.</u> Public Land Survey	T <u>2</u> S R <u>6</u> W	<u>D-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

24 SEP 96 10:35 A.M.

ANNE B. NORLANDER  
CLERK - REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Donald J. Davis, in a field survey on August 21, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Marshall Twp.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Lyon in 1825.  
Resurvey by Gifford in 1890, tile set.  
Tile found by L. Chase in 1937, 3" Oak stake with 1/2" bolt placed over tile.  
Angle iron Post N 3° W 100.65'  
34.3' South of Eastbound track.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found old stake and 4" longbolt on top of tile, 3' underground.  
Accepted as good perpetuation of original corner.

LIBER 1887 PAGE 967

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument over tile.  
South rail of RR track, North 34.3'  
Nail & Tag 6" Hickory S 15° W 14.45'  
Nail & Tag 10" Hickory S 40° E 26.65'  
Nail & Tag 16" Cherry S 35° W 12.35'



Signed by Donald J. Davis  
Surveyor's Michigan License No. 17617

Date September 11, 1996