

**SURVEY &
REMONUMENTATION**

MAR 21 1997

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
COMMISSION
Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED
Date SEPT 18 1996
**CALHOUN COUNTY
REMONUMENTATION.**

For corners in

<u>Calhoun</u> (County)	Located In:	Corner Code #
1. Marshall Twp. Public Land Survey	T <u>2</u> S R <u>6</u> W	<u>E-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

24 SEP 96 10:55 A.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Marshall Twp.

I, Donald J. Davis, in a field survey on August 21, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Lyon in 1825.

Resurvey by Gifford in 1890. Corner is in oak tree, tree found in 1937 by L.W. Chase.

1990 3/4" pipe, 4' long found by Crane in remains of stump. Matched location to N & S and E fence, capped iron set.

10" Cherry S 30° W 22.80'

10" Hickory West 58.66'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found capped iron from Crane witnesses.

Matched location of fences.

Accepted as good establishment of original corner.

LIBER 1887 PAGE 968

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument.

Fence N & S 1' East

Fence East 1' North

Nail & Tag 20" Cherry S 40° W 22.95'

Nail & Tag 12" Hickory S 70° W 42.54'

Nail & Tag Twin 10" Cherry N 10° W 52.82'



Signed by Donald J. Davis
Surveyor's Michigan License No. 17617

Date September 11, 1996