

**SURVEY &
REMONUMENTATION**

MAR 21 1997

APPROVED
Date Sept 18 1996
**CALHOUN COUNTY
REMONUMENTATION.**

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE COMMISSION
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

24 SEP 96 10:55 A.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

Calhoun	Located In:	Corner Code #
(County)		
Marshall Twp.		
1. Public Land Survey	T <u>2 S</u> R <u>6 W</u>	<u>E-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Donald J. Davis, in a field survey on August 27, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey 1825, by Lyon .
Resurvey 1890 by Gifford, tile set.
Tile found by Chase in 1937, set iron pipe.
Angle iron post South 29.4'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found T iron and pieces of tile.
29.5' North of angle iron post.

Accepted as good location of original corner.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Marshall Twp.

LIBER 1887 PAGE 969

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument in monument box 3' North of centerline of paving.
Nail & Tag Power pole North 29.11'
Nail & Tag 42" Maple S 65° W 99.00'
Nail & Tag Power pole N 70° E 98.00'
Angle iron fence post South 29.50'



Signed by Donald J. Davis
Surveyor's Michigan License No. 17617

Date September 9, 1996