

**SURVEY &
REMONUMENTATION**

MAR 21 1997

COMMISSION

APPROVED

Date Oct. 16 1996
**CALHOUN COUNTY
REMONUMENTATION.**

**CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

18 OCT 96 2:28 P.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER **1893** PAGE **302**

Register of Deeds Stamp & File Number

For corners in

<u>Calhoun</u> (County)	Located In:	Corner Code #
<u>Marshall Twp.</u>		
1. Public Land Survey	T <u>2</u> S R <u>6</u> W	<u>F-11</u>
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Marshall Twp.

I, Donald J. Davis, in a field survey on October 2, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Lyon in 1825.
Resurvey by Gifford in 1890, tile set.
Tile found by Chase in 1956.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found tile with stones around. Checked distance from centerline of west bound railroad track.

Accepted as good preservation of original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument with stones around.
Fence and tree row north.
North rail of railroad track South 157.82'
Nail & Tag 42" Maple North 65.75'
Nail & Tag 6" Oak S 25° W 117.55'
Nail & Tag 14" Cherry stump North 135.1'



Signed by Donald J. Davis
Surveyor's Michigan License No. 17617

Date October 15, 1996