

MAR 30 1999

APPROVED

Date 12-9-98 *REC*
**CALHOUN COUNTY
REMONUMENTATION.**

**CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

15 DEC 1998 3:38:00 PM

ANNE D. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER **2087** PAGE **937**

Register of Deeds Stamp & File Number

<u>CALHOUN</u> (County)	Located In:	Corner Code #
MARSHALL	T <u>2S</u> R <u>6W</u>	<u>F-13</u>
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous	S ___ T ___ R ___	_____
Property in Sec.	S ___ T ___ R ___	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael A. Groat, in a field survey on December 7, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		18		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
ORIGINAL SURVEY BY LUCIUS LYON, DEPUTY SURVEYOR, 1825, SET POST, TAM, 7",
N 76 1/2° E, 32 LKS, TAM, 6" N 56° W, 29 LKS.
JAMES GIFFORD, 1891, FOUND STUMPS OF OLD BEARING TREES, SET STAKE, 6" TAM,
N 59° W, 30 LKS, TAM, 8", N 16 3/4 ° W, 66 LKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND HOLLOW TILE WITH STEEL PIN INSIDE AT FENCE INTERSECTION. ACCEPTED THIS AS A FAITHFUL AND CAREFUL PERPETUATION OF THE ORIGINAL MONUMENT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET BERNTSEN MONUMENT WITH CARSONITE MARKER ON NORTH SIDE.
NAIL & TAG IN 6" ASH, WEST, 20.67'
NAIL & TAG IN 8" ASH, S 80° E, 23.80'
NAIL & TAG IN 8" ASH, SOUTH 21.05'
NAIL & TAG IN 10" CHERRY, N 5° E, 11.10'



Signed by *Michael A. Groat*

Date December 4, 1998

Surveyor's Michigan License No. 39079