

MAR 30 1999

**APPROVED**

SECTION

Date 12-9-98 MLL  
**CALHOUN COUNTY  
REMONUMENTATION.**

**CALHOUN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

For corners in

15 DEC 1998 3:37:29 PM

<u>CALHOUN</u> (County)	Located In:	Corner Code #
MARSHALL	T <u>2S</u> R <u>6W</u>	<u>G-13</u>
1. Public Land Survey	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

ANNE B. NORLANDER  
CLERK - REGISTER OF DEEDS

LIBER **2087** PAGE **935**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Michael A. Groat, in a field survey on December 1, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL SURVEY BY LUCIUS LYON, DEPUTY SURVEYOR, 1825, W. OAK, 9", N 19 1/2° E, 70 LKS, W. OAK, 8", N 63° W, 86 LKS.  
JAMES GIFFORD, 1891, FOUND STUMP OF BOTH BEARING TREES, SET STAKE, TAM, 6", N 59° W, 30 LKS, TAM, 8", N 16 3/4° W, 66 LKS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND TILE IN FENCE RUNNING EAST AND WEST. 1" PIPE WAS INSIDE TILE AND THERE WERE SEVERAL LARGE ROCKS AROUND IT. FREDONIA CORNER IS 44.89' EAST.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET BERNTSEN MONUMENT IN PLACE OF TILE.  
NAIL & TAG IN 24" OAK, S 80° W, 10.50'  
NAIL & TAG IN 10" OAK, NORTH 30.10'  
NAIL & TAG IN 8" OAK, S 20° E, 7.5'  
IRON FENCE POST, EAST, 16.30'



Signed by Michael A. Groat

Date 12-10-98

Surveyor's Michigan License No. \_\_\_\_\_