

APPROVED

Date 12/8/99 RRC
CALHOUN COUNTY
REMONUMENTATION

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

For corners in
Marshall Township
Calhoun County

Located In: Corner Code #

- 1. Public Land Survey T 2S R 6W H-13
 T R
 T R
 T R
- 2. Property Controlling S T R
 In Section S T R
- 3. Miscellaneous S T R
 Property in Sec. S T R

17 DEC 1999 2:32:57 PM

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER 2185 PAGE 988

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Scott E. Koch, in a field survey on November 11, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Degree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

November 1825 - G.L.O. Lucius Lyon, Set Quarter Section Post which
a W. Oak 18 in. diam. N1°E, 70 lks. (46.2') dist. &
a W. Oak 24 in. diam. N86°W, 63 lks. (41.58') dist.

1891 - Resurvey James M. Grifford,
Found a large stone with brick around and also the place where one Gov't Tree had recently been removed or stump taken out. Set stake from which
White Oak 10 in. bears S80°E, 10 links (6.6') distance
Hickory 8 in. bears S23°E, 136 links (89.76') distance

1964 - Witness Card Frank K. Holmes, MSHD
Found pointed Blue Rock In fence corner.
30" Twin Wild Cherry - Due North, 58.00'
Concrete Corner Post - N75°W, 1.20'
6" Wild Cherry - N85°E, 30.75'

June 27, 1991 - William A. Worth, PS #19009,
In an unrecorded survey Job No. 2344-7.63, show corner, but gives no description of corner or witnesses to it.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Searched at the apparent location of the corner and Found Pointed Blue Stone Set In Concrete. Chiseled away stone in an attempt to find tile or brick as described in Resurvey. Dug to a depth of 1.5'± and continued to find smaller stones, more concrete and tree roots. It appeared as though any evidence of the tile and brick were destroyed when the Concrete Corner Post was set, and that the pointed blue stone was intending to mark the corner. Accepted the pointed blue stone as the best available evidence of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced Pointed Blue Stone with 3/4" Form Pin with 2" Aluminum Disk stamped Calhoun Co. Remon. & PS 41103.
Set Nail & Tag in W'ly face of Twin 20" Shingle Oak, N10°W, 13.12'
Set Nail & Tag in S'ly face of 18" Cherry, N85°E, 3.95'
Set Nail & Tag in S'ly face of 12" Cherry, N45°E, 34.74'
SE'ly face of 14" Diameter concrete fence post, N45°W, 0.55'

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by Scott E. Koch

Date November 16, 1999

Surveyor's Michigan License No. 41103

SURVEY &
REMONUMENTATION

MAR 13 2000

SECTION

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995

