

**SURVEY &  
REMONUMENTATION**

MAR 21 1997

COMMISSION

**APPROVED**  
Date Oct. 16 1996  
**CALHOUN COUNTY  
REMONUMENTATION.**

CALHOUN COUNTY REMONUMENTATION  
**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

18 OCT 96 2:31 P.M.

ANNE D. NORLANDER  
CLERK - REGISTER OF DEEDS

LIBER 1893 PAGE 308

Register of Deeds Stamp & File Number

Calhoun (County)	Located In:	Corner Code #/
Marshall Township		
1. Public Land Survey	T 2 S R 6 W	I-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William K. Crane, in a field survey on October 2, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

Original Government Survey	Resurvey	LCRC, L. 992, P. 45, 1972
Lucius Lyon, 1825:	By James Gifford, 1890:	by Milt Dekeyser:
16" R. Oak.....S62½E.....52 links	Found hole of old stake in fence lines.	Tile in fence corner.
6" D.O.....N88W.....25 links	6" Yellow Oak.....North.....16 links	16" Oak.....South.....57.0'
	12" White Oak.....S5°E.....23 links	W. Cherry clump...N70E.....20.3'
		Maple clump.....S70E.....28.1'
		26" Oak stump.....S05E.....15.48'
		Utility Pole.....West.....211.53'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 1/2" iron inside hollow tile at fence corner and two ties remaining from the 1972 LCRC.

16" Oak.....South.....57.0'  
26" Oak stump.....S05°E.....15.48'

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set standard Calhoun County Remonumentation Monument (Bernsten Monument) over top of broken portion of clay tile that remained.

Set nail & tag in 12" Cherry.....South.....7.96'  
Set nail & tag in 8" Cherry.....S75°E.....60.60'  
Set nail & tag in 10" Cherry.....N85°E.....59.77'  
26" Oak stump.....S05°E.....15.48'  
East edge of gravel drive.....West.....5'

This is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William K. Crane Date October 16, 1996  
Surveyor's Michigan License No. 29243

