

**SURVEY &
REMONUMENTATION**

MAR 21 1997

COMMISSION

APPROVED
Date Oct. 16, 1996
**CALHOUN COUNTY
REMONUMENTATION.**

**CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

18 OCT 96 2:31 P.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER 1893 PAGE 307

Register of Deeds Stamp & File Number

For corners in

Calhoun (County)	Located In:	Corner Code #
Marshall Township		
1. Public Land Survey	T 2 S R 6 W	I-12
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
3. Miscellaneous	S T R	
Property in Sec.	S T R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William K. Crane, in a field survey on October 14, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original Government Survey Lucius Lyon, 1825:	Resurvey By James Gifford, 1890:	LCRC, L. 1106, P. 914, 1975 by Robert Carr:
15" W. Oak.....N69°E.....98 links 20" B. Oak.....S24°W.....42 links	Found long pointed stone set when government bearing trees were standing. Set stake. 14" Yellow Oak.....S84°E.....44 links 4" Osage Orange.....N15°W.....4½ links	Pointed sandstone in fence line East. 16" Osage Orange.....N15°W.....2.7' 6" Yellow Oak.....S84E.....28.1' 1"± East of fence line North 24" Osage Orange.....North.....3.3' 24" Oak.....S88E.....28.2' 28" Oak.....East.....39.94'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found pointed stone as described above with 1" iron beside it. Excavation revealed the iron was driven inside a hollow clay tile. Held the location of the hollow clay tile as the true position for this corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced tile, pointed stone and 1" iron with standard Calhoun County Remonumentation Monument (Bernsten Monument).

- Set nail & tag in 20" Osage Orange.....North.....3.27'
- Set nail & tag in 12" W. Cherry.....N35°E.....28.62'
- Set nail & tag in 24" Oak.....S75°E.....27.59'
- Set nail & tag in 18" Oak.....West.....22.68'

This is accepted as a careful and faithful perpetuation of the position of the original corner.



Signed by William K. Crane Date October 16, 1996
Surveyor's Michigan License No. 29243