

**SURVEY &  
REMONUMENTATION**

MAR 21 1997

**COMMISSION**

**APPROVED**  
Date Oct 16, 1996  
**CALHOUN COUNTY  
REMONUMENTATION.**

CALHOUN COUNTY REMONUMENTATION  
**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

18 OCT 96 2:30 P.M.

ANNE B. NORLANDER  
CLERK - REGISTER OF DEEDS

LIBER 1893 PAGE 305

Register of Deeds Stamp & File Number

For corners in

Calhoun (County)	Located In:	Corner Code ##
Marshall Township	T 2 S R 6 W	J-13
1. Public Land Survey	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William K. Crane, in a field survey on October 14, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Original Government Survey	Resurvey	LCRC, L. 1106, P. 914, 1976
<u>Lucius Lyon, 1825:</u>	<u>By James Gifford, 1890:</u>	<u>by Robert Carr:</u>
12" W. Oak.....N25°E.....85 links	Placed corner in line with fence North and 6 links West of the line fence South.	1/2" iron stake in centerline of bituminous road in line with fence North.
12" D.O.....N50°W.....41 links	12" W.Oak.....S60°E.....59 links	1 1/2" iron pipe.....East.....3.96'
	6" Yellow Oak.....N54°W.....78 links	Chain link
		fence corner.....North.....32.88'
		Chain link
		fence corner.....S5°E.....35.95'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron stake in centerline of bituminous surface as recorded in 1976 LCRC above.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Replaced 1/2" iron stake with standard Calhoun County Remonumentation Monument (Bernsten Monument) and a monument box.

1/2" rerod.....North.....32.95'  
Set nail & tag in 16" Maple.....N75°E.....72.54'  
Face of corner steel fence  
post for 6'high chain link  
fence.....S5°E.....35.87'  
1/2" iron for Fredonia Cor.....East.....3.86'

This is accepted as the best available evidence of the position of the original corner.



Signed by William K. Crane Date October 16, 1996  
Surveyor's Michigan License No. 29243