

**APPROVED**  
 Date 8-17-94  
**CALHOUN COUNTY**  
**REMONUMENTATION.**

CALHOUN COUNTY REMONUMENTATION  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
 CALHOUN COUNTY  
 RECORDED

18 AUG 94 12:07 P.M.

ANNE B. NORLANDER  
 CLERK - REGISTER OF DEEDS

For corners in

Calhoun  
 (County)

Located In: \_\_\_\_\_ Corner Code #/ # \_\_\_\_\_

1. Public Land Survey T 2 S R 6 W K-12  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

I, Donald J. Davis, in a field survey on August 13, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Resurvey, 1890 by James M. Gifford.  
 Set post.  
 10" Elm S 84° E, 44 links  
 12" Oak S 30½° E, 82 links

**SURVEY &  
 REMONUMENTATION**

OCT 24 1994

COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found ½" iron in monument box.  
 Held as good perpetuation of original corner.

LIBER 1763 PAGE 754

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument in monument box.  
 Top nut fire hydrant N 30° E, 113.71'  
 Fence corner N 30° W, 206.30'  
 Nail & Spotter in U.P., West, 45.68'  
 Nail & Spotter in U.P., S 30° W, 208.3'



Signed by Donald J. Davis  
 Surveyor's Michigan License No. 17617

Date August 17, 1994