

**CALHOUN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**APPROVED**  
Date Nov. 22 1995  
**CALHOUN COUNTY  
REMONUMENTATION.**

For corners in <u>Calhoun</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>2S</u> R <u>6W</u>	<u>M-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

4 DEC 95 2:30 P.M.

ANNE B. NORLANDER  
CLERK - REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Michael A. Groat, in a field survey on May 30, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

Gifford, 1890 Re-survey	Original survey
12" Oak, S 16½° W, 96 Links	Lyon, 1825
15" White Oak, N 71° W, 18 Links	

1966 Chase made reference to using the corner.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2			
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

Marshall

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found Iron rod 6 links North of corner for Marengo Twp. Dug but found no evidence of life. This corner has been used by local surveyors and was accepted as a good perpetuation of the original monument.

REMONUMENTATION

FEB 22 1996

COMMISSION

LIBER 1834 PAGE 267

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set a Harrison monument, from which:

Steel fence post, East, 26.65'  
Nail and spotter in U.P., S 33° E, 82.0'  
Nail and spotter in 12" Apple, S 20° W, 97.6'  
Nail and spotter in 6" Apple, N 10° E, 141.2'



Signed by Michael A. Groat  
Michael A. Groat  
Surveyor's Michigan License No. 39079

Date 11-18-95