

APPROVED
 to Smith & Davis
CALHOUN COUNTY
REMONUMENTATION.
 For corners in

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 CALHOUN COUNTY
 RECORDED

18 AUG 94 12:07 P.M.

ANNE B. NORLANDER
 CLERK - REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Calhoun (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>2</u> S R <u>6</u> W	<u>M-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Donald J. Davis, in a field survey on August 13, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Resurvey, 1890 by James M. Gifford.
 Large stone.
 10" Apple S 31½° W, 48 links
 16" Hickory S 86° W 76 links

**SURVEY &
 REMONUMENTATION**
 OCT 24 1994
 COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found capped iron, Ronald Keller, #20707, in road.
 No other evidence found.
 Held as good perpetuation of original corner.

LIBER 1763 PAGE 750

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument and monument box.
 Nail & Spotter in 10" Maple S 80° W, 39.33'
 Nail & Spotter in 10" Maple S 10° W, 46.10'
 Nail & Spotter in U.P. N 30° E, 54.00'
 Nail & Spotter 8 " Maple N 30° W, 89.10'



Signed by Donald J. Davis
 Surveyor's Michigan License No. 17617

Date August 17, 1994