

APPROVED

Date 8-17-94
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

18 AUG 94 12:06 P.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

For corners in
Calhoun
(County)

Located In: Corner Code #

- 1. Public Land Survey T 2 S R 6 W M-13
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Donald J. Davis in a field survey on August 13, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- Resurvey, 1890 by James M. Gifford Pike, 10-24-68, Dekeyser & Assoc.
- Set stake. 2 1/2" Angle iron fence post
- 16" Oak N 1° E 236 links. 8" Maple N 10° E, 10'
- 8" Oak N 89° W 100 links. 6" Hickory West 22.7'

SURVEY &
REMONUMENTATION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Found angle iron post called for by Pike. Found tile 2.5' West of Post.
- Held tile for corner. Accepted as true corner from resurvey.

OCT 24 1994
COMMISSION

LIBER 1763 PAGE 749

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set Berntsen monument with carsonite marker beside.
- Nail & Spotter 12" Ash South, 3.35'
- Nail & Spotter 10" Ash West, 5.55'
- Nail & Spotter 10" Ash S 80° E, 12.45'
- Nail & Spotter 6" Ash N 5° E, 4.90'



Signed by Donald J. Davis
Surveyor's Michigan License No. 17617

Date August 17, 1994