

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED
 Date Oct. 14 1995
CALHOUN COUNTY
REMONUMENTATION.

For corners in
Calhoun

(County)

Located In:

Corner Code #

<u>Emmett Township</u>			
1. Public Land Survey	T <u>2S</u>	R <u>7W</u>	<u>C-9</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

STATE OF MICHIGAN
 CALHOUN COUNTY
 RECORDED

26 OCT 95 10:14 A.M.

Register of Deeds Stamp & File Number
 CLERK - REGISTER OF DEEDS

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Donald J. Davis, in a field survey on November 10, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original survey in 1826 by Sibley.	Corner used by MDSH on survey of I-94.
Resurvey in 1889 by Hodgeman.	8" Oak N 3° W 33.24'
Tile	18" Oak N 43° E 35.50'
10" White Oak S 82° W 42 links.	Iron Post South 24.52'
12" White Oak N 31° E 53 links.	

LCRC recorded on July 12, 1995 in Liber 1810, page 10.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" iron pipe over clay tile, 2.5 feet under surface of road.
 Accepted as true corner.

SURVEYOR
 REMONUMENTATION

FEB 22 1996

COMMISSION

LIBER 1828 PAGE 63

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument over tile with monument box.

- NE corner of RR rail post South 24.78'
- Nail & Tag Utility pole North 41.20'
- Nail & Tag 20" Oak N 40° E 35.60'
- Nail & Tag 14" Elm S 45° E 30.80'
- Nail & Tag 50" White Oak S 45° W 33.15'



Signed by Donald J. Davis
 Donald J. Davis
 Surveyor's Michigan License No. 17617

Date October 9, 1995