

APPROVED

Date 9-15-99 *RCC*
CALHOUN COUNTY
REMONUMENTATION.
For corners in

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

<u>CALHOUN</u> (County)	Located In:	Corner Code #
EMMETT TOWNSHIP		
1. Public Land Survey	T <u>2S</u> R <u>7W</u>	<u>E-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

29 SEP 1999 10:30:15 AM

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER **2164** PAGE **712**

Register of Deeds Stamp & File Number

I, ROBERT R. CARR, in a field survey on AUGUST 4, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL CORNER SET BY SYLVESTER SIBLEY 1826.

RESURVEY BY F. HODGMAN 1889, FOUND STAKE AT ANGLE OF BOARD FENCE AT POINT WHERE MR. MILLER SAYS HE HAS KNOWN THE CORNER FOR A NUMBER OF YEARS, SET POST AND MARKED HICKORY 12" N1W 138, Y OAK 8 N88E 141.

PLAT OF FAIRFAX LIBER 5, PAGE 45 BY HERBERT J. ADAMS 1917 INDICATES POINT "A" OF PLAT AT CORNER COMMON TO SECTIONS 4, 5, 8 & 9

WITNESS BY CARR TO 1-1/4" IRON PIPE 1968 AND UPDATED 1978.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 5/8" IRON 1 FOOT MORE OR LESS BELOW SURFACE FOR POINT "A" OF PLAT OF FAIRFAX. THIS IRON MATCHES WITNESS BY CARR FROM 1968 AND 1978 TO 1-1/2" PIPE. ALSO FOUND A 36" OAK N86°E 93.5 FEET TO CENTER WHICH APPEARS TO BE RESURVEY WITNESS BY HODGMAN (Y OAK 8 N88E 141 LKS).

REPLACED 5/8" IRON WITH BERNTSEN MONUMENT IN MONUMENT BOX.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN MONUMENT IN MONUMENT BOX
NW CORNER OF HOUSE NO. 134, S52°W, 41.65 FEET
NE CORNER OF HOUSE NO. 134, S05°W 42.53 FEET
36" OAK, N86°E 71.08 FEET, SET NAIL AND SPOTTER
12" MAPLE, N01°W 46.30 FEET, SET NAIL AND SPOTTER

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.



Signed by [Signature]
Surveyor's Michigan License No. 20704 ROBERT R. CARR

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

SURVEY &
REMONUMENTATION

MAR 13 2000

SECTION