

APPROVED

Date 11/17/99 *PRC*
CALHOUN COUNTY
REMONUMENTATION.
For corners in

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

3 DEC 1999 2:42:40 PM

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER **2182** PAGE **424**

Register of Deeds Stamp & File Number

<u>CALHOUN</u> (County)	Located in:	Corner Code #
EMMETT TOWNSHIP		
1. Public Land Survey	T <u>2S</u> R <u>7W</u>	<u>E-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

I, ROBERT R. CARR, in a field survey on NOVEMBER 15, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL CORNER SET BY SYLVESTER SIBLEY, D.S. 1826.
RESURVEY BY F. HODGMAN, 1889.
WITNESS CARD BY H.K. WHITNEY, 1901, CALLS FOR GOVERNMENT CORNER, DUG AND FOUND OLD ROOTS AND LOCATED STUMP OF H.E. WHITNEY, SET STAKE S39°W 56 LINKS, ALSO FOUND ROOTS OF OTHER WITNESSES, LISTS FOUR WITNESSES.
WITNESS CARD BY C.R. SMITH, MSHD, 1962, FROM WITNESSES 3/4 IRON PIPE.
SURVEY CERTIFICATE BY CHASE 1968 CALLS FOR CORNER TO BE 381.25 FEET NORTH OF CENTERLINE OF MICHIGAN AVENUE.
L.C.R.C. BY ROBERT P. KIRKLEY, P.S. NO. 38118, 3/9/98 LIBER 2008, P. 296, SET REFERENCE IRON 4.200 METERS SOUTH OF CORNER.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND REFERENCE MONUMENT PER L.C.R.C. LIBER 2008, PAGE 296.
ACCEPTED LOCATION ESTABLISHED BY KIRKLEY L.C.R.C. LIBER 2008, PAGE 296 AS BEST EVIDENCE OF ORIGINAL CORNER.
REPLACED KIRKLEY'S REFERENCE IRON WITH A BERNTSEN MONUMENT IN MONUMENT BOX.
TRUE LOCATION OF CORNER IS UNDER A MOBILE HOME.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN MONUMENT IN MONUMENT BOX 13.78 FEET (4.20 METERS) SOUTH OF TRUE CORNER ON LINE BETWEEN CORNERS E-4 AND E-5.
WITNESSES TO REFERENCE MONUMENT.
EAST FACE OF 30" OAK, S26°W 154.65 FEET, NAIL AND WASHER
SOUTHEAST FACE OF 30" OAK, S60°W 75.00 FEET, NAIL AND WASHER
SOUTH FACE OF 30" OAK, N85°W 53.22 FEET, NAIL AND WASHER
CENTER 3 PUNCH HOLES IN NORTH FACE OF FENCE POST, S88°E 59.86 FEET.

THIS LOCATION IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

Signed by *Robert R. Carr*

Surveyor's Michigan License No. 20704 ROBERT R. CARR

Date NOV. 17 1999

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

SURVEY & REMONUMENTATION

MAR 13 2000

SECTION

