

APPROVED

Date 11/17/99  
CALHOUN COUNTY  
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>CALHOUN</u> (County)	Located In:	Corner Code #
EMMETT TOWNSHIP	T <u>2S</u> R <u>7W</u>	<u>E-5</u>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

3 DEC 1999 2:42:29 PM

ANNE B. NORLANDER  
CLERK - REGISTER OF DEEDS

LIBER 2182 PAGE 423

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, ROBERT R. CARR, in a field survey on AUGUST 4, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL CORNER SET BY SYLVESTER SIBLEY D.S. 1826  
RESURVEY F. HODGMAN 1889  
H.K. WHITNEY 1901 FOUND SECTION CORNER O.K. 8-9-16-17  
9 FT. B. ASH STAKE 6" N&S X 7" E&W, STANDS 4 FT OUT OF GROUND AND  
BLAZED ON NORTH AND SOUTH, WHITNEY LISTS 5 BEARING TREES AND STATES  
THAT CORNER IS 1.38 LINKS S. & 14'11" E. OF TILE OF RESURVEY.  
(NOTE: H.K. WHITNEY 1901 LOCATION IS PASTED OVER RESURVEY NOTES  
FROM OFFICE OF CRANE LAND SURVEYING.)  
WITNESS CARD C.E. SMITH, M.D.S.H. 1962 FROM OFFICE OF CRANE LAND  
SURVEYING, 1-1/2" PIPE, 2-1/2' ABOVE GROUND.  
WITNESS CARD FROM CRANE LAND SURVEYING/DEKEYSER & ASSOCIATES BY  
R.R.C. 1972, FOUND 1-1/2" PIPE FROM MSHD WITNESSES.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

ALL H.K. WHITNEY WITNESSES ARE GONE.  
FOUND 1-1/2" IRON PIPE PER MSHD 1962 AND SUBSEQUENT WITNESS CARDS BY SMITH AND R.R.C.  
DUG AND PROBED FOR TILE OR OTHER EVIDENCE OF CORNER, NONE FOUND.  
FLARED TOP OF PIPE AND PLACED BERNTSEN REMONUMENTATION MONUMENT OVER.

SURVEY &  
REMONUMENTATION  
MAR 13 2000  
SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN MONUMENT OVER 1-1/2" IRON PIPE WITH  
CARSONITE WITNESS POST ON NORTH SIDE.  
14" MAPLE, N04°W 83.92 FEET, SET NAIL AND SPOTTER  
10" MAPLE, N82°E 7.17 FEET, SET NAIL AND SPOTTER  
15" MAPLE, S40°E 68.60 FEET, SET NAIL AND SPOTTER  
10" MAPLE, S83°W 43.75 FEET, SET NAIL AND SPOTTER

THIS LOCATION IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

Signed by [Signature]  
Surveyor's Michigan License No. 20704 ROBERT R. CARR

Date NOV 17 1999

