

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED
 Date Nov. 30, 1995
CALHOUN COUNTY
REMONUMENTATION.

For corners in

<u>Calhoun</u> (County) Emmett Twp.	Located In:	Corner Code #
1. Public Land Survey	T <u>2</u> S R <u>7</u> W	E-9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
 CALHOUN COUNTY
 RECORDED
 4 DEC 95 2:20 P.M.
 ANNE B. NORLANDER
 CLERK - REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

I, Donald J. Davis, in a field survey on October 4, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Sibley in 1826.
 Resurvey by Hodgeman in 1889. Clay tile set.
 Plat of Woodland Beach 1922, corner used. Plat in Liber 6 on page 16.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" pipe at surface. Dug and found clay tile 15" under surface in back yard of house. Checked good to lot irons found.
 Accepted as good preservation of original corner.

CONCRETE
 REMONUMENTATION

LIBER 1834 PAGE 247

FEB 22 1996

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument in concrete.
 Nail & Tag 38" Oak S 70° E 33.48'
 Nail & Tag 32" Oak South 50.88'
 Nail & Tag 30" Oak N 40° E 27.28'
 Nail & Tag 20" Maple N 10° E 54.84'



Signed by Donald J. Davis
 Donald J. Davis
 Surveyor's Michigan License No. 17617

Date November 7, 1995