

APPROVED

Date 9-15-99 RRC
CALHOUN COUNTY
REMONUMENTATION
For corners in

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

<u>CALHOUN</u> (County)	Located In:	Corner Code #
EMMETT TOWNSHIP		
1. Public Land Survey	T <u>2S</u> R <u>7W</u>	<u>F-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

29 SEP 1999 10:29:54 AM

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER **2164** PAGE **711**
Register of Deeds Stamp & File Number

I, ROBERT R. CARR, in a field survey on AUGUST 4, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL CORNER SET BY SYLVESTER SIBLEY D.S. 1826.

RESURVEY BY F. HODGMAN 1889, FOUND OLD STAKE FROM STUMP OF U.S. BEARING TREE AND SET TILE.

SUPERVISORS PLAT OF DEXTER LAKE BY A.H. CHASE 1927 CALLS FOR NE CORNER OF PLAT TO BE N1/4 POST, SECTION 9.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND BOTTOM OF BROKEN OFF MONUMENT AT NE CORNER OF THE SUPERVISORS PLAT OF DEXTER LAKE, BELOW SURFACE AND IN CENTER OF DIRT BIKE TRAIL.

ACCEPTED MONUMENT AS PERPETUATION OF CORNER AND REPLACED WITH BERNTSEN MONUMENT PLACED WELL BELOW SURFACE WITH BROKEN CONCRETE AROUND IT.

SURVEY &
REMONUMENTATION

MAR 13 2000

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN MONUMENT BELOW SURFACE WITH BROKEN CONCRETE AROUND.

CARSONITE WITNESS POST, S40°W 8.0 FEET
UTILITY POLE MARKED D.E. 94, S85°E 30.88 FEET, SET NAIL AND SPOTTER
UTILITY POLE MARKED #88, N85°W 56.71 FEET, SET NAIL AND SPOTTER
SOUTH TOWER LEG AT GROUND, N06°W 166.50 FEET
24" OAK, S38°E 157.20 FEET, SET NAIL AND SPOTTER

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by [Signature]
Surveyor's Michigan License No. 20704 ROBERT R. CARR

