

**CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

APPROVED
Date Nov. 20 1995
**CALHOUN COUNTY
REMONUMENTATION.**

For corners in
Calhoun

	(County) Emmett Twp.	Located In:	Corner Code #
1. Public Land Survey		T <u>2</u> S R <u>7</u> W	F-9
		T _____ R _____	_____
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

I, Donald J. Davis, in a field survey on October 4, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Original survey in 1826 by Sibley.
Resurvey by Hodgeman in 1889, clay tile set.
Iron stake found by DeKeyser in 1972.
Recorded in L.C.R.C., Liber 992 on page 51.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1" pipe stake as called for in recorded L.C.R.C.
Dug and found clay tile 18" under road surface.
Accepted as good preservation of original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set Berntsen monument in monument box in bituminous road.
Nail & Tag Power pole South 33.72'
Nail & Tag 36" Oak N 10° W 23.25'
Nail & Tag 18" Maple S 50° E 35.63'
Nail & Tag 18" Oak N 55° E 63.54'
In line with fences North & South.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

4 DEC 95 2:18 P.M.


ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER **1834** PAGE **245**

REMONUMENTATION

FEB 22 1996

COMMISSION



Signed by Donald J. Davis
Surveyor's Michigan License No. #17617

Date November 3, 1995