

**APPROVED**  
 Date 11-12-96  
**CALHOUN COUNTY**  
**REMONUMENTATION.**

**CALHOUN COUNTY REMONUMENTATION**  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
 CALHOUN COUNTY  
 RECORDED

For corners in

<u>Calhoun</u> (County)	Located In:	Corner Code #/
<b>Emmett Twp</b>		
1. Public Land Survey Sec 4	T <u>2</u> S R <u>7</u> W	<u>G-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

19 NOV 96 1:53 P.M.

ANNE B. NORLANDER  
 CLERK - REGISTER OF DEEDS

LIBER **1899** PAGE **601**

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Emmett Township

I, Robert R. Carr, in a field survey on October 23, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.; S. Sibley, 1826.

Resurvey; Hodgeman, 1889, found stake at intersection of bearings N60-1/2W 8-1/2 links from Yellow Oak 16" bearing tree of resurvey of R.H. Merritt set post (tile) no other trees near.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 2'x3" solid tile over another 3" solid tile, 3'x5/8" rebar with cap no. 29245 beside tile, also old spline gear laying beside tile.  
 Accepted tile as true perpetuation of corner.

**SURVEY & REMONUMENTATION**

MAR 21 1997

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced top tile with Berntsen Calhoun County Remonumentation Monument with Carsonite witness post 1 foot south.

- Nail & spotter Southerly side U-Pole N85°E 49.12 feet.
- Nail & spotter Westerly side twin 18"-20" Oak S26°E 64.55 feet.
- Nail & spotter Easterly side 28" Oak N28°E 119.63 feet.
- Nail & spotter Westerly side 6" Oak S40°W 14.40 feet.



Signed by Robert R. Carr  
 Surveyor's Michigan License No. 20704

Date November 8, 1996