

# APPROVED

Date 10-20-99 R.R.C.

CALHOUN COUNTY  
REMONUMENTATION

**CALHOUN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **2182** PAGE **426**

For corners in

<u>CALHOUN</u>	Located In:	Corner Code #
(County)		
EMMETT TOWNSHIP		
1. Public Land Survey	<u>T.2S R.7W</u>	<u>G-7</u>
	T. R.	
	T. R.	
	T. R.	
2. Property Controlling in Section	S. T. R.	
	S. T. R.	
3. Miscellaneous Property in Sec.	S. T. R.	
	S. T. R.	

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

3 DEC 1999 2:43:30 PM

Register of Deeds & Mortgages Number  
CLERK - REGISTER OF DEEDS

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Michael A. Groat, in a field survey on October 5, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:


ORIGINAL SURVEY, SYLVESTER SIBLEY, 1826, SET POST, W. OAK, 12", NORTH 65° EAST, 80 LINKS, W. OAK, 16", SOUTH 38° WEST, 45 LINKS.  
RE-SURVEY, 1889, F. HODGEMAN, FOUND OLD STAKE NORTH 38° EAST, 45 LINKS FROM HOLE WHERE W. OAK BEARING TREE ROTTED OUT. SET POST  
1957, MSHD, 3" PIPE, 8" HICKORY, SOUTH 20° EAST, 9.51'; 8" OAK, NORTH 50° EAST, 10.95'  
1973, C. PIKE, P.S.; TILE & C.P. CO. MARKER 9" HICKORY, SOUTH 30° WEST, 9.40' 10" OAK, EAST, 15.92'  
SURVEY BY R. CARR, P.S. FOUND C.P. CO MARKER, NAIL & SPOTTER, 16" ASH, SOUTH 18° WEST, 46.60'  
NAIL & SPOTTER, 14" OAK, SOUTH 40° EAST, 23.36'; NAIL & SPOTTER, 14" OAK, NORTH 60° EAST, 15.74';  
NAIL & SPOTTER, 14" CHERRY, NORTH 55° WEST, 18.06'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3" X 6" C.P. CO PIPE IN CONCRETE. 0.3' SOUTH FOUND FIRECLAY TILE, FOUND A SECOND TILE BENEATH ACCEPTED THE FIRECLAY AS A CAREFUL & FAITHFUL PERPETUATION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED TILE & C.P. CO. MARKER WITH A BERNTSEN MONUMENT.  
NAIL & TAG IN 14" HICKORY, SOUTH 40° WEST, 9.80'  
NAIL & TAG IN 16" BLACK CHERRY, NORTH 55° WEST, 18.85'  
NAIL & TAG IN 14" BLACK OAK, NORTH 60° EAST, 15.62'  
NAIL & TAG IN 14" CHERRY, NORTH 55° WEST, 18.20'  
CARSONITE MARKER, SOUTH 65° EAST, 1.55'



Signed by [Signature]  
Surveyor's Michigan License No. 39079

Date 10/12/99

SURVEY &  
REMONUMENTATION

MAR 13 2000

SECTION