

APPROVED

Date 10-20-99 RKC
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

3 DEC 1999 2:43:06 PM

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER 2182 PAGE 425

Register of Deeds Stamp & File Number

<u>CALHOUN</u> (County)	Located In:	Corner Code #
EMMETT	<u>T 2S R 7W</u>	<u>H-7</u>
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael A. Groat, in a field survey on October 5, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:


ORIGINAL SURVEY, SYLVESTER SIBLEY, 1826, SET POST 40.00 CHAINS, B. OAK, 15' SOUTH 24° WEST, 21 LINKS; B. OAK, 18", NORTH 88° EAST, 37 LINKS
RE-SURVEY, F. HODGEMAN, 1887, FOUND OLD STAKE AND STUMP OF BEARING TREE SET POST, MAPLE 14", NORTH 76° EAST, 20 LINKS, W. OAK, 8" SOUTH 38° EAST 48 LINKS
1957, MSHD, 1" IRON STAKE OVER TILE, 10" COTTONWOOD, NORTH 45° WEST, 18.10'; APPLE, NORTH 55.5'; 45" OAK, SOUTH 50° WEST, 51.10'; 12" TWIN CHERRY, NORTH 50° EAST, 27.44'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" X 4' PIPE NEXT TO LARGE ROCK EXCAVATED & FOUND THIS CORNER FALLS ON A STEEP SLOPE CREATED WHEN I-94 WAS CONSTRUCTED.
ACCEPTED THE PIPE AS THE BEST EVIDENCE OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET BERNTSEN MONUMENT IN PLACE OF PIPE
NAIL & TAG IN 8" LOCUST, SOUTH 40° EAST, 35.40'
NAIL & TAG IN 10" SHAGBARK HICKORY, NORTH 75° EAST, 87.55'
NAIL & TAG IN 3" HICKORY, NORTH 10° EAST, 8.75'
NAIL & TAG IN 8" APPLE, NORTH, 55.3'
CARSONITE MARKER, SOUTH 45° WEST, 1.67'



Signed by [Signature]
Surveyor's Michigan License No. 39079

Date 10/12/99

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 22, 1971
REVISED MAY 14, 1975
REVISED JAN. 1983
REVISED OCT., 1988

SURVEY &
REMONUMENTATION
MAR 13 2000
SECTION