

APPROVED

Date 2-2-94
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Calhoun</u> (County)	Located In:	Corner Code #
Emmett Township	Sec. 15	
1. Public Land Survey	T <u>2S</u> R <u>7W</u>	<u>I-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

CLERK-REGISTER
CALHOUN COUNTY, MICH.
ANNE B. NORLANDER
FEB 4 3 11 PM 94
RECORDED

Register of Deeds Stamp & File Number

I, Daniel M. Ryan, in a field survey on November 16, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: Sibley, 1826	Resurvey: Hodgeman	1978-Gertz of DeKeyser Assoc.
13" W. Oak, N19°W, 10 links	Stake in centerline road	Reset R.R. spike from John Alden witnesses to hex mon. over tile.
26" W. Oak, N83°E, 49 link	W Oak, 18", S20°E, 97 links	32" Oak, S30°±E, 27.79 feet
	W. Oak, 12", N77½°E, 156 links	2.7 feet South of painted centerline
		NE corner trans. box, S5°E, 39.95 feet
		10" Maple, S50°W, 49.34 feet
		In line fences North & South

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Railroad spike: 3.15 feet South of painted centerline.
 32" Oak, S30°±E, 27.8 feet
 In line with North and South fences.
 Offset and Searched for hex mon & tile.
 Found no evidence. Accepted Gertz's location as a good perpetuation of the true location.

SURVEY &
REMONUMENTATION

OCT 27 1994

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed spike and set Bernstein monument with drill hole, stamped license number 34975 in top and placed mon box around corner.
 Witnesses:
 Painted centerline F Drive North, 3.15 feet.
 U-pole, N10°W, 31.6 feet.
 14" Hickory, S50°W, 49.3 feet.
 32" Oak, S30°±E, 27.8 feet.
 6" Ash, N70°E, 99.3 feet.
 In line with fences N&S.

LIBER 1730 PAGE 826

Signed by Daniel M. Ryan Date November 16, 1993

Surveyor's Michigan License No. 34975