

APPROVED

Date 2-2-94
**CALHOUN COUNTY
REMONUMENTATION.**

**CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

CLERK-REGISTER
CALHOUN COUNTY, MICH.
ANNE B. NORLANDER

FEB 4 3 12 PM '94

RECORDED

For corners in
CALHOUN
(County)

Located In: Corner Code ##

- | | | |
|------------------------------------|-------------------------|------------|
| 1. Public Land Survey | T <u>2S</u> R <u>7W</u> | <u>J-7</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Michael A. Groat in a field survey on January 12, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Hodgeman 1889 Re-Survey	No date of Name
Found stake hole and used remains of both bearing trees	West side of large stone
Set tile	8" Hickory, SE, 38.0'
8" Hickory West 9 1/2° East, 43 lks	8" Elm, N8°E, 26.4'
4" Hickory North 44°West, 60 lks	8" Oak, SW, 39.5'

Noted as gone by D. Dek.
12-14-78

1991 King Ryan and Assoc.
Set Iron
8" Oak, N50°W, 135.2'
8" Maple S20°W, 37.1'
8" Maple S30°E, 42.4'
4" Oak, S60°E, 85.2'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1991 No evidence of corner or witness trees. Dug in three separate locations and found nothing. Set iron midway on line between I-7 and K-7.

**SURVEY &
REMONUMENTATION**

OCT 27 1994

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument and monument box and stamped license # 39079 and corner information in top.

Witnesses:

- Nail and spotter in 8" Oak, N50°W, 135.2'
- Nail and spotter in 8" Maple, S20°W, 37.1'
- Nail and spotter in 8" Maple, S30°E, 42.2'
- Nail and spotter in 4" Oak, S60°E, 85.2'

LIBER 1730 PAGE 831



Signed by Michael A. Groat
Surveyor's Michigan License No. 39079

Date 2-2-94