

APPROVED

Date 4-20-94
CALHOUN COUNTY
REMONUMENTATION

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Calhoun (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>2S</u> R <u>7W</u>	<u>K-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
Register of Deeds Stamp File Number
RECORDED

A	B	22 APR 94	4:54 P.M.	J	K	L	M
2	6	ANNE B. NORLANDER		2			1
3		CLERK - REGISTER OF DEEDS					
4	7	8	9	10	11	12	
5							
6	16	17	16	15	14	13	
7							
8	19	20	21	22	23	24	
9							
10	30	29	28	27	26	25	
11							
12	31	32	33	34	35	36	
13							

I, MICHAEL A. GROAT, in a field survey on April 2, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- | | | |
|---------------------------|-----------------------------|---------------------------------|
| Resurvey 1889, Hodgman | 1951 | 1975 Pike |
| Found old stake hole | concrete monument over tile | Iron in monument box |
| Placed tile in hole | 5" Elm, SW, 72.51' | 2" twin oak, 73.74' |
| 16" Oak S67°W 1.17 chains | 7" Twin Oak, S60°E 72.55' | 2" Oak, West 32.2' |
| 6" Oak S69°W 1.01 chains | 14" Oak, West 39.2' | 4" Iron corner post, West 36.6' |
| | 4" Iron post, West 36.6' | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found iron in monument box. Box and iron were cemented in ground. Held this as corner.

SURVEY &
REMONUMENTATION

LIBER 1743 PAGE 407

OCT 27 1994

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" iron in concrete in monument box.

- 8' East of centerline of 11 Mile road
- 2' South of centerline of F Drive North
- NAIL AND SPOTTER in U.P. S15°E, 77.1'
- NAIL AND SPOTTER in 24" Oak, N85°W, 39.2'
- Stop sign, N45°E, 35.5'



Signed by Michael A. Groat

Date 4-20-94

Surveyor's Michigan License No. _____