

APPROVED

Date 4-20-94
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Calhoun
(County)

	Located In:	Corner Code =#
1. Public Land Survey	T <u>2S</u> R <u>7W</u>	<u>K-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED
Register of Deeds Stamp & File Number
22 APR 94 4:54 P.M.

I, MICHAEL A. GROAT, in a field survey on April 2, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Resurvey 1885, Hodgeman No name or date
Found Brg. tree stump Tile
Set post from it 24" B.O. N 57° W 38.2'
30" B.O. S 50° W 55.0'
8" Hick. N 44° E 46.3'

A	B	CANNE E. NORBANKER	J	K	L	M
2	CLERK	5	REGISTER OF DEEDS			
3						
4	7	8	9	10	11	12
5						
6	18	17	16	15	14	13
7						
8	19	20	21	22	23	24
9						
10	30	29	28	27	26	25
11						
12	31	32	33	34	35	36
13						

Road Commision
Gone-1977

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found iron in pavement set by Dekeyser. Held this as a good perpetuation of corner

SURVEY &
REMONUMENTATION

LIBER 1743 PAGE 408

OCT 27 1994

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set Bertsen monument and monument box.

NAIL AND SPOTTER in 14" Oak, S 45° W, 80.3'
NAIL AND SPOTTER in 18" Hickory, N 45° E, 54.7'
NAIL AND SPOTTER in 20" Oak, N 10° E, 109.5'
Face of telephone stantion S 45° E, 56.9'



Signed by Michael A. Groat

Date 4-20-94

Surveyor's Michigan License No. _____