

SURVEY & REMONUMENTATION

MAR 21 1997

COMMISSION

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

24 SEP 96 10:53 A.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

Register of Deeds Stamp & File Number

APPROVED

Date Aug. 21 1996
**CALHOUN COUNTY
REMONUMENTATION.**

Calhoun County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Calhoun</u> (County)	Located In:	Corner Code #
1. <u>Emmett Twp.</u> Public Land Survey	T <u>2</u> S R <u>7</u> W	<u>L-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Emmett Twp.

I, Donald J. Davis, in a field survey on August 2, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Survey by Sibley 1826.
Resurvey by Hodgeman, 1889, Tile set.
DeKeyser found tile 1972, Set 1/2" iron rod.
15" Oak S 54° W 39.57'
Iron Post N 04° E 27.43'
Iron Post South 28.30'
SE Corner house foundation N 20° W 98.25'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron rod and 30" of tile on centerline of road.
Checked good for witnesses of DeKeyser.
Accepted as good perpetuation of original corner location.

LIBER 1887 PAGE 961

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument in monument box, centerline of road East and West in line with tree row North and South.

SE corner house foundation N 20° W 98.25'
Nail & Tag 12" Maple N 40° E 51.80'
Nail & Tag 12" Maple South 27.83'
Nail & Tag 28" Oak S 40° W 39.57'



Signed by Donald J. Davis
Donald J. Davis
Surveyor's Michigan License No. 17617

Date August 16, 1996