

**SURVEY &  
REMONUMENTATION**

MAR 21 1997

COMMISSION

**APPROVED**

Date MAY 15, 1996

**CALHOUN COUNTY  
REMONUMENTATION.**

**CALHOUN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

7 JUN 96 9:49 A.M.

ANNE B. NORLANDER  
CLERK - REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in  
Calhoun

(County)

Emmett Twp.

Located In:

Corner Code #

- |                                       |                           |            |
|---------------------------------------|---------------------------|------------|
| 1. Public Land Survey                 | T <u>2</u> S R <u>7</u> W | <u>L-7</u> |
|                                       | T _____ R _____           | _____      |
|                                       | T _____ R _____           | _____      |
|                                       | T _____ R _____           | _____      |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____   | _____      |
|                                       | S _____ T _____ R _____   | _____      |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____   | _____      |
|                                       | S _____ T _____ R _____   | _____      |
| 4. Lot No. _____, Recorded Plat _____ |                           |            |
| 5. Private Claims _____               |                           |            |

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Donald J. Davis, in a field survey on April 22, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Original Survey by Sibley in 1826.  
Resurvey in 1889 by Hodgmann-Tile set.  
Cultivated field destroyed tile.  
Corner reset in 1979 by Davis using Plat of "Wagner Acres".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" iron as set in 1979 and used by DeKeyser in 1981.  
North and South fence West 2.5'  
Fence West.  
31" Oak North 76.67'

LIBER 1865 PAGE 706

Accepted as location of corner as reset and used in area.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument with rocks around.  
Nail & Tag 8" Cherry North 197.25'  
Nail & Tag 14" Cherry West 205.3'  
1" Pipe S 40° W 26.30'  
6" Cedar N 55° W 187.51'



Signed by Donald J. Davis  
Surveyor's Michigan License No. 17617

Date May 15, 1996