

SURVEY & REMONUMENTATION

MAR 21 1997

COMMISSION

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

7 JUN 96 9:49 A.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

Register of Deeds Stamp & File Number

APPROVED
Date MAY 15, 1996
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Calhoun</u>		Located In:	Corner Code #
<u>(County)</u> <u>Emmett Twp.</u>			
1. Public Land Survey	T <u>2</u> S R <u>7</u> W		<u>M-5</u>
	T _____ R _____		_____
	T _____ R _____		_____
	T _____ R _____		_____
2. Property Controlling in Section	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Donald J. Davis, in a field survey on April 22, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Sibley in 1826.
Resurvey in 1889 by Hodgemann.
Tile set
 $\frac{1}{2}$ " pipe and fence post set by DeKeyser in 1972.
8" Tamarack N 80° W 19.0'
N. edge of pavement South 15.0'
8" Poplar S 70° E 4.52'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found $\frac{1}{2}$ " pipe and fence post 15' North of north edge pavement.
Old witnesses gone.

Accepted as location of corner as reset and used in area.

LIBER 1865 PAGE 705

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument with carsonite marker at point.
Nail & Tag 12" Tamarack S 22° W 60.98'
Nail & Tag 12" Poplar N 01° E 9.10'
Nail & Tag 8" Birch N 80° E 29.43'
Nail & Tag 22" Maple N 75° W 59.64'
North edge pavement South 15.0'



Signed by Donald J. Davis Date May 15, 1996
Surveyor's Michigan License No. 17617