

**SURVEY &
REMONUMENTATION**

MAR 2 1 1997

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

24 SEP 96 10:56 A.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

Register of Deeds Stamp & File Number

APPROVED

Date SEPT 18 1996
**CALHOUN COUNTY
REMONUMENTATION.**

For corners in	<u>Calhoun</u> (County)	Located In:	Corner Code <u>##</u>
1.	<u>Emmett Twp.</u> Public Land Survey	T <u>2S</u> R <u>7W</u>	<u>M-6</u>
		T _____ R _____	_____
		T _____ R _____	_____
		T _____ R _____	_____
2.	Property Controlling in Section	S _____ T _____ R _____	_____
		S _____ T _____ R _____	_____
3.	Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
		S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

EMMETT TWP.

I, Donald J. Davis, in a field survey on August 10, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Sibley in 1826.
12" White Oak S 12° W 102 links
6" Tamarack North 3.3 links
Resurvey by Hodgeman in 1889.
M.D.S.H. 1" pipe found 1957
9" Oak S 46° W 70.28' 8" Oak S 2° W 48.07'
8" Oak S 12° W 49.03' 8" Cherry S 16° E 48.13'
Corner 76.10' N of centerline I-94 @ Station 679 + 89.06. M.D.S.H. plans

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found no witnesses to corner.
Reset Emmett corner using centerline of I-94 and stationing on highway plans.
Corner falls 25.21 feet North of centerline of Westbound lane I-94.
Accepted this location as no other plan or witnesses available to relocate corner.
Construction of I-94 destroyed all witnesses and corner.

LIBER 1887 PAGE 973

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument 6" under gravel shoulder on I-94.
Centerline of westbound slab South 25.21'.
Station 679 + 89.06 M.D.S.H. plans project control section 13082
Nail & Tag 14" Elm N 20° E 100.22'
Angle iron Post in fence N 70° W 151.48'



Signed by Donald J. Davis
Surveyor's Michigan License No. 17617

Date August 19, 1996