

REMONUMENTATION

FEB 22 1996

COMMISSION

CALHOUN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED

Date Oct 18 1995
CALHOUN COUNTY
REMONUMENTATION.

For corners in

Calhoun (County)	Located In:	Corner Code #/
1. Public Land Survey	T 2 S R 8 W	C-2
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

26 OCT 95 10:02 A.M.

Register of Deeds Stamp & File Number
CLERK REGISTER OF DEEDS

I, William K. Crane, in a field survey on October 16, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Government
Field Notes (S. Sibley
26):

" W. Oak N51°E 99 links
" B. Oak S54°E 40 links

Resurvey-F. Hodgman (1886):

Found old stake hole in Section
line & remains of a U.S. Bearing
Set Post.

8" Hickory N75°E 49 links
4" W. Oak N18°W 50 links

Records from Dekeyser & Assoc.
indicate 1" iron pipe (undated)
& a railroad spike in 1970.
Corner was witnessed by City of
Battle Creek during construction
of Hill Brady Road in the 1980's
& recorded in L. 1583, P. 551 for
Battle Creek-Fort Custer Urban
Renewal Plat No. 2.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found P.K. nail per witnesses of L.C.R.C. recorded in L. 1583, P. 551. All witnesses still good.

LIBER 1828 PAGE 40

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced P.K. nail with standard Calhoun County Remonumentation Monument (Bernsten Monument) and a monument box.

-Centerline Road	East	9'
-Centerline of light pole	N20°W	91.50'
-No parking sign	N25°E	94.58'
-NE Cor Inlet	S40°W	20.98'
-NW Cor Inlet	S60°E	36.90'

This is accepted as the best available evidence of
the position of the original corner.

Signed by William K. Crane
William K. Crane
Surveyor's Michigan License No. 29243

Date October 18, 1995

