

REMONUMENTATION  
 FEB 22 1996  
 COMMISSION

CALHOUN COUNTY REMONUMENTATION  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED  
 Date Sept 20 1995  
 CALHOUN COUNTY  
 REMONUMENTATION.

For corners in

CALHOUN (County)	Located In:	Corner Code #
BATTLE CREEK CITY		
1. Public Land Survey	T 2 S R 8 W	D-5
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN  
 CALHOUN COUNTY  
 RECORDED  
 26 OCT 95 10:14 A.M.  
 ANNE E. NORLANDER  
 CLERK - REGISTER OF DEEDS  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, ROBERT R. CARR, in a field survey on SEPTEMBER 1, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5		17	16	15	14	13							
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

SOUTH 1/4 POST SECTION 8 TOWN 2 SOUTH RANGE 8 WEST  
 ORIGINAL CORNER SET BY S. SIBLEY 1826.  
 F. HODGEMAN 1889 FOUND OLD STAKE AT INTERSECTION OF FENCES AND SET POST (TILE).  
 TILE FOUND 1931 BY MICHIGAN STATE HIGHWAY DEPARTMENT.  
 TILE FOUND 1961.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND TILE ON NORTH SIDE OF ANGLE IRON POST WITH BROKEN CONCRETE AROUND.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

RE-PLACED TILE WITH CALHOUN COUNTY ~~REMONUMENT~~ MONUMENT (BERNTSEN MONUMENT) WITH CARSONITE POST ON NORTH SIDE.  
 NAIL & SPOTTER IN SOUTHEAST SIDE OF 8" OAK N52°E 19.93 FEET.  
 NAIL & SPOTTER IN SOUTHWEST SIDE OF 12" OAK S35°E 11.90 FEET.  
 NAIL & SPOTTER IN WEST SIDE OF 10" OAK S5°E 29.30 FEET.  
 NAIL & SPOTTER IN NORTH SIDE OF 12" OAK S79°W 18.70 FEET.  
 NAIL & SPOTTER IN NORTHWEST SIDE OF 12" OAK S28°W 24.93 FEET.  
 NAIL & SPOTTER IN NORTHEAST SIDE OF 10" OAK N45°W 16.10 FEET.

LIBER 1828 PAGE 60



Signed by [Signature]  
 ROBERT R. CARR  
 Surveyor's Michigan License No. 20704

Date SEPTEMBER 20, 1995