

250

REMONUMENTATION

FEB 22 1996

COMMISSION

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED

Date Nov 23 1995

CALHOUN COUNTY
REMONUMENTATION
STATE OF MICHIGAN

CALHOUN COUNTY
RECORDED

4 DEC 95 2:26 P.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

CALHOUN
(County)

Located In:

Corner Code #/

BATTLE CREEK CITY

1. Public Land Survey	T	<u>2S</u>	R	<u>8 W</u>	<u>E-3</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	_____
	S	_____	T	_____	_____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3					3								
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, ROBERT R. CARR, in a field survey on OCTOBER 24, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO, SIBLEY, 1826,
- HODGEMAN, 1887, FOUND OLD STAKE HOLE AT INTERSECTION OF ROADS, BEARING TREES GONE, SET TILE.
- M.S.H.D. 1961 FOUND 1-1/2" PIPE WITH BRICK AROUND.
- M.S.H.D. 1977 FOUND PIPE.
- L.C.R.C. BY CRANE, 09/09/91, FOUND 1-1/2" PIPE.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- FOUND 1-1/2" PIPE DISTURBED BY RECENT CONSTRUCTION, WITH PIECES OF BRICK AT BOTTOM.
- RE-ESTABLISHED LOCATION FROM CRANE & M.S.H.D WITNESSES.

LIBER 1834 PAGE 257

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET BERNTSEN CALHOUN COUNTY REMON. MONUMENT WITH CARSONITE WITNESS POST ON SOUTH SIDE AND STONES AROUND MONUMENT.
- CONCRETE MONUMENT, S32°E, 28.50 FEET.
- ANGLE IRON CORNER POST, S87°E, 106.42 FEET.
- CONCRETE MONUMENT, S56°W, 162.24 FEET.
- TWIN 10"-14" MAPLE, S11°E, 120.58 FEET. (NAIL & SPOTTER)
- TOP NUT OF F-HYDRANT, S86°E, 171.28 FT.



Signed by Robert R. Carr

Date NOVEMBER 17, 1995

Surveyor's Michigan License No. 20704