

SURVEY & REMONUMENTATION

APR 26 1995

APPROVED

ate 10-19-94  
CALHOUN COUNTY  
REMONUMENTATION.

COMMISSION  
CALHOUN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Calhoun (County) Located In: Corner Code I-6

1. Public Land Survey	T <u>2</u> S R <u>8</u> W	<u>I-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED  
25 OCT 94 9:02 A.M.  
ANNE B. NORLANDER  
CLERK - REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

Donald J. Davis, in a field survey on March 28, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Tile set in resurvey, 1887 by Hodgman. Tile found in 1963 by L.W. Chase, 3/4" pipe to surface.  
Face concrete Light base South 3.75'.  
Utility pole N 20° E 10.80'  
NE Corner concrete bldg S 35° W 79.30'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" pipe over tile.

LIBER 1773 PAGE 882

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen stainless monument with brass cap over tile.  
Face of concrete light base South 3.75'.  
Utility pole N 20° E (P.K. Nail) 10.80'  
Utility pole S 85° W (P.K. Nail) 25.20'  
NE corner concrete blk. bldg. S 35° W 79.30'



Signed by Donald J. Davis  
Surveyor's Michigan License No. 17617

Date March 29, 1994