

**SURVEY &
REMONUMENTATION**

1993

COMMISSION

**CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

Nov 19 2 22 PM '93

CLERK-REGISTER
CALHOUN COUNTY, MICH.
ANNE B. NORLANDER

For corners in

<u>Calhoun</u> <small>(County)</small>	Located In:	Corner Code #
Battle Creek Township	Section 27	East 1/4 corner
1. Public Land Survey	T 2S R 8W	I-10
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27	●	26		25		
11													
12	31		32		33		34		35		36		
13													

I, Daniel M. Ryan, in a field survey on November 16, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Resurvey by Hodgeman:	1957 - Unknown:	1975-LCRC# L1081 P632:
Found stone 24"x10"x8" w/brick	Concrete Monument	Concrete Mon found by Cutcher
On line with fence North	20" Elm, SE, 56.5 feet	Conc. Anchor Post, N26.75'
Set tile: Apple 12", S40-3/4°W,	Conc. Anchor post, N26.75'	22" Maple, S 23.00 feet
64.5 links	9" Maple, SE, 23.00'	18" Walnut, N45°E, 42.00 feet
Hickory, 4", S53°E,	14" Walnut, N45°E, 42.00'	U-pole, N17°E, 26.21 feet
62 links	U-pole, N17°E, 26.21'	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found concrete monument in blacktop surface, 6" deep.
Concrete anchor post, N26.75 feet
U-pole, N17°E, 26.21 feet
14" Walnut, N45°E, 42.0 nail in Northwest side.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set Bernstein monument with drill hole in monument box. Stamped 34975 in top.

Witnessed as:
Concrete anchor post, N26.75 feet.
U-pole, N17°E, 26.21 feet
14" Walnut, N45°E, 42.00 feet
U-pole, S69°E, 61.79 feet

LIBER 1716 PAGE 450



Signed by Daniel M. Ryan
Surveyor's Michigan License No. 34975

Date November 16, 1993