

**CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

APPROVED
Date Nov. 22 1995
**CALHOUN COUNTY
REMONUMENTATION.**

For corners in <u>Calhoun</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>2S</u> R <u>8W</u>	<u>K-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

4 DEC 95 2:30 P.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael A. Groat, in a field survey on October 2, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Battle Creek

A. Description of original monument and accessories and/or subsequent restoration:
1826 - Sibley Original Survey Re-survey
8" White Oak, S 41° E, 60 Lks Hodgman, 1886
9" White Oak, N 58° W, 120 Lks.

1966 - No Name
W. Oak, S 82° E, 30.52'
R. Oak, N 35° E, 48.84'
U.P., N 30° W, 61.40'
Oak, S 40° W, 53.96'
Oak, East, 32.94'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Corner was removed during re-construction of Capital Ave. It was offset by Dan Ryan, City Surveyor before construction began. We re-set the corner using this offset information.

CORNER &
REMONUMENTATION

LIRER 1834 PAGE 264

FEB 22 1996

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument an monument box, from which:
Nail and spotter in U.P., N 21° E, 94.95'
Nail and spotter in U.P., N 18° W, 61.40'
Nail and spotter in 30" Oak, S 44° W, 53.65'
Nail and spotter in U.P., S 9° E, 75.60'



Signed by Michael A. Groat
Surveyor's Michigan License No. 39079

Date 11-17-95