

SURVEY & REMONUMENTATION

1993

COMMISSION

**CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

Nov 19 2 22 PM 93

CLERK-REGISTER
CALHOUN COUNTY, MICH.
ANNE B. NORLANDER

For corners in

<u>Calhoun</u> (County)	Located In:	Corner Code #
<u>Battle Creek Township</u>	Sec. 26	
1. Public Land Survey	T <u>2S</u> R <u>8W</u>	<u>K-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Daniel M. Ryan, in a field survey on November 16, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
 GLO: by Merritt 1979-Pike, City B.C.
 RESURVEY: Hodgeman, 1887 1" iron rod
 Set fire clay in place of original U-pole, N60°E, 43.17'
 stake. U-pole, S60°E, 37.78'
 In line with fence East U-pole, S70°W, 49.78'
 Bearing trees by R.B. Merritt & Guy pole, S30°W, 77.68'
 stnading
 Red Oak, 14", N43°W, 39 links
 Hickory, 12", S38°W, 44 links

1984-Enz, MDOT, LCRC L1319, P86
 1" iron S4 Westerly painted center-line.
 S55°E, 37.77', U-pole
 Placed Mon box
 U-pole, N65°E, 43.21'
 U-pole, S25°W, 77.68'
 U-pole, S75°W, 49.75'
 Easterly 5.4' from centerline of Capital Avenue

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" iron in concrete in monument box.
 U-pole, S60°E, 37.78 feet. Found nail & spotter.
 U-pole, S70°W, 49.78 feet. Found nail & spotter.
 Guy-pole, S30°W, 77.65 feet. Found nail & spotter.

This corner has been used by others and is a good perpetuation of the true corner location.

LIBER 1716 PAGE 449

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted 1" iron in concrete as a long-standing monument and left it in the monument box.
 Witnesses as follows:
 U-pole, S60°E, 37.78 feet.
 U-pole, S70°W, 49.78 feet.
 Guy-pole, S30°W, 77.65 feet.
 Hydrant top nut, N30°E, 75.10 feet.



Signed by [Signature] Date November 16, 1993

Surveyor's Michigan License No. 34975